RUHAT BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE,
.E.I.LAYOUT, BAGALAGUNTE, HESARAGHATTA MAIN ROAD, BANGALORE-560 073

E/DD/WO/ 63/15-16

Office of the Executive Engineer,
Dasarahalli Division,
Dated: 24/3/2016

# Work Order

ri. S.Kemparaju,
43, 3rd block, 3rd stage,
.G.Halli, Basaveshwara nagara
angalore-79

| | | | |
|---|---|---|---|
| ame of Work: | Improvements and construction of CC road from Mahakavi Kuvempu road to Urdu school road in Dasarahalli Ward no.15 | | |
| st Cost: | 10.00 | Lakhs | Item No.47 |
| b Code: | 015-16-000008 | | PCode-1771 |
| lministrative Approval: | EE/DD/AS/21/15-16, Dt:04.01.2016. | | |
| chnical Sanction: | EE/DD/TS/21/15-16, Dt:04.01.2016. | | |
| nder Notification No& Date: | BBMP/EE/DD/Ten/01/2014-15, Dt:04.01.2016 | | |

-:-:-

By Virtue of having Executed Agreement and the same has been accepted by the Engineer/Executive Engineer for the Work mentioned in reference, for the tender of Rs 840622.00 (Rupees Eight Lakh Fourty Thousand Six Hundred Twenty Two (Which is 15.07% Below/Above SR of 2015-16) you are hereby instructed to ed to execution of the said work in accordance with the contract documents. ltation with the Concerned Ward Assistant Executive Engineer, and complete the as per agreement within 90 days from the date of issue of this letter,

Yours faithfully,

Executive Engineer,
Dasarahalli Division,
BBMP, Bangalore.

**to:**

Addl.commissioner, Dasarahalli Zone, for kind information.
Chief Engineer. Dasarahalli Zone, for kind information.
E.E., Q.C. for Kind information.
A.E.E. (Shettyhalli / Dasarahalli / P.I.A / Hegganahalli) Sub Division, A copy of Accepted Rate list is enclosed for your information and guidance.
ವಾರ್ಡ್ ಮಟ್ಟದ ಕಾಮಗಾರಿ ಸ್ಥಾಯಿ ಸಮಿತಿ, ರವರ ಮಾಹಿತಿಗಾಗಿ.
Office copy.

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division,
No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 **Indent No.20443**

**SCHEDULE-B**

**NAME OF WORK:** Improvements and construction of CC road from Mahakavi Kuvempu road to Urdu school road in Dasarahalli Ward no.15

| Sl. No | Description of work | Unit | Qty | Rates Quoted by Contractor **Kemparaju S** | | |
|---|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) | Cont. AMOUNT |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specfication & as per direction of Engineer-in-charge | Cum | 63.54 | 250.0 | Rupees Two Hundred Fifty Only | 15885.00 |
| 2 | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specfication & as per direction of Engineer-in-charge | Cum | 41.44 | 4940.0 | Rupees Four Thousand Nine Hundred Forty Only | 204713.60 |
| 3 | Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement design mix M30 at 360 kg per cum, with 25mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizer at 3lts conforming to IS 9103-1999 reaffirmed 2008. coarse and fine aggregate conforming to IS:383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing, compound, finishing to lines and grades as per drawing complete as per specfication & as per direction of Engineer-in-charge | Cum | 81.52 | 5500.0 | Rupees Five Thousand Five Hundred Only | 448360.00 |

S. Kemparaju
Signature of the Contractor

Executive Engineer

RUHAT BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE,
I.E.I.LAYOUT, BAGALAGUNTE, HESARAGHATTA MAIN ROAD, BANGALORE-560 073

E/DD/WO/ 63 /15-16

Office of the Executive Engineer,
Dasarahalli Division,
Dated: 24/3/2016

# Work Order

ri. S.Kemparaju,
43, 3rd block, 3rd stage,
.G.Halli, Basaveshwara nagara
angalore-79

| | | | |
|---|---|---|---|
| ame of Work: | Improvements and construction of CC road from Mahakavi Kuvempu road to Urdu school road in Dasarahalli Ward no.15 | | |
| st Cost: | 10.00 | Lakhs | Item No.47 |
| b Code: | 015-16-000008 | | PCode-1771 |
| dministrative Approval: | EE/DD/AS/21/15-16, Dt:04.01.2016. | | |
| chnical Sanction: | EE/DD/TS/21/15-16, Dt:04.01.2016. | | |
| nder Notification No& Date: | BBMP/EE/DD/Ten/01/2014-15, Dt:04.01.2016 | | |

-:-:-

By Virtue of having Executed Agreement and the same has been accepted by the Engineer/Executive Engineer for the Work mentioned in reference, for the tender of Rs 840622.00 (Rupees Eight Lakh Fourty Thousand Six Hundred Twenty Two (Which is 15.07% Below/Above SR of 2015-16) you are hereby instructed to ed to execution of the said work in accordance with the contract documents. ltation with the Concerned Ward Assistant Executive Engineer, and complete the as per agreement within 90 days from the date of issue of this letter,

Yours faithfully,

Executive Engineer,
Dasarahalli Division,
BBMP, Bangalore.

**to:**

Addl.commissioner, Dasarahalli Zone, for kind information.
Chief Engineer. Dasarahalli Zone, for kind information.
E.E., Q.C. for Kind information.
A.E.E. (Shettyhalli / Dasarahalli / P.I.A / Hegganahalli) Sub Division, A copy of Accepted Rate list is enclosed for your information and guidance.
ವಾರ್ಡ್ ಮಟ್ಟದ ಕಾಮಗಾರಿ ಸ್ಥಾಯಿ ಸಮಿತಿ, ರವರ ಮಾಹಿತಿಗಾಗಿ.
Office copy.

| | | | | | | |
|---|---|---|---|---|---|---|
| 4 | Providing T.M.T. steel reinforcement for R.C.C. work including straightening cutting, bending, hooking, placing in position, lapping and (or welding wherever required, trying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specfication & as per direction of Engineer-in-charge | Tonne | 2.7 | 62000.0 | Rupees Sixty Two Thousand Only | 167400.00 |
| 5 | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specfication & as per direction of Engineer-in-charge | Cum | 63.54 | 67.1 | Rupees Sixty Seven and Ten Paise Only | 4263.53 |
| | | | | | Total | 840622.13 |
| | | | | | Percentage | -15.07% |

S. Kemparaju
Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer